

Lessons learned from one of New Zealand's most challenging civil engineering projects: rebuilding the earthquake damaged pipes, roads, bridges and retaining walls in the city of Christchurch 2011 - 2016.

Critical Risk 1 Health and Safety Toolbox – service strikes

Story: Health and Safety

Theme: Programme Management

A document which outlines how to work safely around underground services, created to discuss with site staff at on-site "toolbox talks".

This document has been provided as an example of a tool that might be useful for other organisations undertaking complex disaster recovery or infrastructure rebuild programmes.

For more information about this document, visit www.scirtlearninglegacy.org.nz

















This work is licensed under a Creative Commons Attribution 3.0 New Zealand License.

The authors, and Stronger Christchurch Infrastructure Rebuild Team (SCIRT) have taken all reasonable care to ensure the accuracy of the information supplied in this legacy document. However, neither the authors nor SCIRT, warrant that the information contained in this legacy document will be complete or free of errors or inaccuracies. By using this legacy document you accept all liability arising from your use of it. Neither the authors nor SCIRT, will be liable for any loss or damage suffered by any person arising from the use of this legacy document, however caused.



















Health and Safety Toolbox 1

Critical risk - Service Strikes

What is a service strike and how can I get hurt?

A service strike is when our work penetrates or compromises as service such as power, gas, water, pipe, phone line etc.

Service strikes are our <u>number 1 critical risk</u> because of the potential consequences of a strike:

- Fatality through electrocution or explosions
- Traumatic body injuries including burns, fractures and paralysis
- Interruption of vital services to the public or service providers affecting those on dialysis, health care centres, and critical communication services.

How can we prevent a service strike?

- Ensure everyone on site is trained for reading service plans and locating services
- Ensure everyone understands the job's detailed Risk Assessment prior to work starting
- Only use As Built service plans that are less that 30 days old
- Only start work once:
 - Services have been located with GPR
 - Services have been clearly marked out
 - After seeing and confirming all the services on site (by potholing, slot trenches and drawings
- Only use hydro or vacuum excavation for potholing
- Use "goal posts", or similar, as visual reminders for Overhead services
- Ensure there is a spotter at all times
- Use engineered support and protection for exposed services





